

## GENERAL NOTES:

- \* 1.) BEGINNING OF TEMPORARY CUL-DE-SAC. ALL CURBING TO BE CONCRETE CONSTRUCTED AS PER CITY STANDARDS.
  - 2.) TEMPORARY ASPHALT CURBING WILL BE PERMITTED ONLY IF:
  - i.) THE ADJACENT LANDS FALL UNDER THE SAME OWNERSHIP. AND
  - II.) THERE IS AN APPROVED PLAN OF SUBDIVISION SHOWING THE INTENT OF THE ROADWAY CONTINUING.
  - 3.) MINIMUM PAVEMENT THICKNESS:

    - iii.) GRANULAR = 400mm TO 100% S.P.D.
  - 4.) CUL-DE-SAC DRAINAGE SHALL BE PROVIDED WITH A MINIMUM LONGITUDINAL GRADIENT OF 0.4%.
  - 5.) MINIMUM 3% CROSS SLOPE AT CUL-DE-SAC.
  - 6.) TEMPORARY CUL-DE-SAC TO HAVE A MINIMUM 9.5M RADIUS.
  - 7.) DEAD END BARRICADE WITH SIGN REQUIRED AS SHOWN. TRAFFIC OPERATIONS TO APPROVE SIGN.

## CITY OF WINDSOR

ENGINEERING DEPARTMENT

## TEMPORARY CUL-DE-SAC FOR (20 METRE MINIMUM RIGHT OF WAY)

DR'N BY: AJC	DATE: AUGUST, 2011
REVISION:	CH'KD BY: P. UBENE
CH'KD BY:	PASSED BY:



AS-545-A