

GENERAL NOTES:

- * 1.) BEGINNING OF TEMPORARY CUL-DE-SAC. ALL CURBING TO BE CONCRETE CONSTRUCTED AS PER CITY STANDARDS.
 - 2.) TEMPORARY ASPHALT CURBING WILL BE PERMITTED ONLY IF:
 - i.) THE ADJACENT LANDS FALL UNDER THE SAME OWNERSHIP. AND
 - II.) THERE IS AN APPROVED PLAN OF SUBDIVISION SHOWING THE INTENT OF THE ROADWAY CONTINUING.
 - 3.) MINIMUM PAVEMENT THICKNESS:
 - I.) BASE ASPHALT $\left. \begin{array}{l} \text{I.Sufface asphalt} \\ \end{array} \right\} \text{ as per the adjacent road design}$
 - iii.) GRANULAR = 400mm TO 100% S.P.D.
 - 4.) CUL-DE-SAC DRAINAGE SHALL BE PROVIDED WITH A MINIMUM LONGITUDINAL GRADIENT OF 0.4%.
 - 5.) MINIMUM 3% CROSS SLOPE AT CUL-DE-SAC.
 - 6.) TEMPORARY CUL-DE-SAC TO HAVE A MINIMUM 9.5M RADIUS.
 - 7.) DEAD END BARRICADE WITH SIGN REQUIRED AS SHOWN. TRAFFIC OPERATIONS TO APPROVE SIGN.
- ** 8.) LAND CONVEYANCE REQUIRED UNTIL SUCH TIME THE ROAD IS CONTINUED. LAND TO BE TRANSFERRED BACK TO THE OWNER WHEN ROAD IS CONTINUED.
 - 9.) CONVEYED LAND TO BE TREATED AS A TYPICAL BOULEVARD REQUIRING A 3% FALL.

CITY OF WINDSOR

ENGINEERING DEPARTMENT

TEMPORARY CUL-DE-SAC FOR (15 METRE RIGHT OF WAY)

DR'N BY: AJC DATE: AUGUST, 2011

REVISION: CH'KD BY: P. UBENE

CH'KD BY: PASSED BY:

CITY ENGINEER AS-545-B