

S-40
**INSTALLATION METHOD OF TRAFFIC SIGNAGE DISTURBED BY
CONSTRUCTION**

TABLE OF CONTENTS

40.01.	SCOPE OF WORK.....	1
40.02.	REFERENCES	1
40.03.	MATERIALS.....	1
40.04.	EQUIPMENT	1
40.05.	CONSTRUCTION.....	2
40.06.	QUALITY ASSURANCE – N/A.....	2
40.07.	MEASUREMENT FOR PAYMENT – N/A	2
40.08.	BASIS FOR PAYMENT.....	2

40.01. SCOPE OF WORK

This specification covers the requirements for the removal and replacement of existing traffic signage during construction.

40.02. REFERENCES

This specification refers to the following standards, specifications, or publications:

- AS-538

40.03. MATERIALS

The Contractor shall supply all materials.

40.04. EQUIPMENT

The Contractor shall supply all equipment.

40.05. CONSTRUCTION

Prior to the commencement of construction, the Contractor shall call Traffic Operations (519-255-6292) and schedule an on-site meeting with the Engineer and Supervisor of Signs and Markings, to carry out an inventory of all existing signage by location. At this time the Contractor shall make the Supervisor of Signs and Markings aware of any signage, which will need to be removed to facilitate construction. All signage required to be removed shall be done so by the Contractor. The signs shall be delivered to Public Works – Traffic Operations at 1269 Mercer Street. **Any signs damaged, deemed unusable or not returned by the Contractor shall be replaced at his cost as deemed by the Supervisor of Signs and Markings.**

Should any Stop Signs or Street Name Signs require removal, the Contractor shall install temporary signs by placement of a 50 gallon barrel, filled with sand or gravel as per Figure 3 in drawing AS-538. Traffic Operations shall approve the temporary location of the barrel and sign.

When construction has reached the stage at which all signage may be reinstalled, the Contractor shall contact the Supervisor of Signs and Markings at Traffic Operations (519-255-6292) and schedule a on-site meeting to review the entire project site. **At this time, the contractor shall supply the necessary labour and equipment to install all required stanchions and posts supplied by Traffic Operations.**

The Contractor shall note that no road is to be opened to traffic until Stop Signs and Street Name Signs have been installed in their permanent locations.

40.06. QUALITY ASSURANCE – N/A

40.07. MEASUREMENT FOR PAYMENT – N/A

40.08. BASIS FOR PAYMENT

Payment for the above and all ancillary work required shall be at the lump sum price bid in the Form of Tender, as no additional payment for this work will be made.